



DEMOLITION PLAN NOTES

- 1 COMPLETELY REMOVE BOTH TOILET ROOM WALLS, DOORS, WATER CLOSETS, PLUMBING FIXTURES AND FLOOR TILE.
- 2 PROPERLY SHORE ANY EXISTING WALL AND CEILING/ROOF STRUCTURE TO REMAIN. INSTALL NEW STRUCTURAL SUPPORT. REMOVE MAIN ENTRANCE AND PORTION OF EXTERIOR WALL TO OPEN UP SPACE FOR NEW NARTHEX.
- 3 REMOVE WINDOW AND WALL BELOW WINDOW TO EXTEND OPENING TO THE FLOOR. OPENING TO BE ENTRY TO NEW TOILET ROOM.
- 4 PROPERLY SHORE ANY EXISTING WALL AND CEILING/ROOF STRUCTURE TO REMAIN. INSTALL NEW STRUCTURAL SUPPORT. REMOVE PORTION OF WALL FROM FLOOR TO BOND BEAM ABOVE. OPENING TO BE NEW DOOR INTO NEW HALLWAY.
- 5 REMOVE EXISTING DOOR AND FRAME.
- 6 REMOVE WALL AT THE BACK OF EXISTING COAT ALCOVE.
- 7 REMOVE WALL AND DOOR BETWEEN TWO EXISTING OFFICES. REMOVE OFFICE CARPET AS WELL. SPACE TO BE NEW TOILET ROOMS.
- 8 REMOVE STOOP AND RAMP.
- 9 DEMO FLOOR AS REQUIRED TO ACCOMMODATE NEW PLUMBING
- 10 REMOVE EXISTING STEEPLE FROM EXISTING ROOF OVER CHURCH SEATING (SHOWN ON ELEVATIONS)
- 11 CUT AND REMOVED EXISTING ASPHALT FOR NEW ADDITION, STOOP, AND RAMP
- 12 EXISTING STONE MULCH TO BE SALVAGED
- 13 EXISTING GRASS TO BE REMOVED
- 14 APPROXIMATE LINE OF BASEMENT WALL BELOW

20 MAIN FLOOR PLAN
SCALE 1/4" = 1'-0" DEMOLITION

Verify all existing site conditions

REVISIONS:

NO.	DATE	DESCRIPTION

SHEET INDEX:
FIRST FLOOR
DEMOLITION PLAN

Copyright © 2017
Idest House, Inc.

DRAWN	APPROVED
RCN	df
MAY 2, 2017	

A200
G667-BID_170511.dwg