



REBALANCE EXISTING
15 TON ROOFTOP UNIT
TO 6000 CFM SUPPLY,
4500 CFM RETURN,
AND 1500 CFM O.A.

18x4 DOUBLE DEFLECTION
SUPPLY REGISTER...ADJUST
FRONT AND BACK BLADES
TO 30" THROW...BALANCE
TO 250 CFM.

18x4 DOUBLE DEFLECTION
SUPPLY REGISTER...ADJUST
FRONT AND BACK BLADES
TO 30" THROW...BALANCE
TO 250 CFM.

18x4 DOUBLE DEFLECTION
SUPPLY REGISTER...ADJUST
FRONT AND BACK BLADES
TO 30" THROW...BALANCE
TO 200 CFM.

18x4 DOUBLE DEFLECTION
SUPPLY REGISTER...ADJUST
FRONT AND BACK BLADES
TO 30" THROW...BALANCE
TO 225 CFM.

18x4 DOUBLE DEFLECTION
SUPPLY REGISTER...ADJUST
FRONT AND BACK BLADES
TO 30" THROW...BALANCE
TO 225 CFM.

NOTE: PAINT ALL VISIBLE
DUCTWORK BLACK TO MINIMIZE
OVERALL VISIBILITY FROM FLOOR.
IF DUCTWORK IS NOT VISIBLE
FROM FLOOR DUE TO BEING
RUN ABOVE DECORATIVE OR
LAY-IN CEILINGS THAN IT WILL
NOT REQUIRE PAINTING.

TYPE II DISHWASHER
HOOD FURNISHED BY
OTHERS INSTALLED BY
HVAC CONTRACTOR.

REF-1...FURNISHED
BY OTHERS INSTALLED
BY HVAC CONTRACTOR

REF-3...FURNISHED
BY OTHERS INSTALLED
BY HVAC CONTRACTOR

GAS-FIRED MAKEUP
AIR UNITS NO.1
FURNISHED BY OTHERS.
INSTALLED BY HVAC
CONTRACTOR.

REF-2...FURNISHED
BY OTHERS INSTALLED
BY HVAC CONTRACTOR

TYPE I COOK-LINE
HOOD FURNISHED BY
OTHERS INSTALLED BY
HVAC CONTRACTOR.

TYPE I COOK-LINE
HOOD FURNISHED BY
OTHERS INSTALLED BY
HVAC CONTRACTOR.

OPEN-ENDED
5" HIGH IN
JANITOR CLOSET
50 CFM

EWB-2
120/1
3 K.W.

FWH-1
120/1
3 K.W.

Verify all existing site conditions
REVISIONS:

SHEET INDEX:
H.V.A.C.
FLOOR PLAN

Copyright © 2018
Ideo House, P.C.
DRAWN: J.J.F. APPROVED: J.J.F.
MAY 16, 2018

H-201
714.SD.dwg